

QUOTATION FOR REPAIRING FOR PLUMBING AND SANITARY WORK		
Sl. No.	PARTICULARS	QTY
1	Providing and fixing white parcel in European type water closet with white PVC Low -down cisten including PVC seat cover complete set (Perry/Hindware)	6 SETS
2	Providing and fixing white porcel wash basin with 1/2" C.P. pillar cock , 1/2"C.P. waste , 1 1/4 20" X 16" X 3'o" waste pipe , 1/2" X 2PVC Connector Pipe , 18" X 12" M.S. bracket , complete (Perry/ Hindware).	4 Nos. 2 Nos.
3	Providing & Fixing white porcelin squatting urinal (Perry/Hindware).	2 Nos.
4	(i)Providing & Fixing 1/2" C.P. Bib cock (ESSCO - Delux). (ii)Providing & Fixing Mirror with Ply back 5'0" X 3'0" (iii)Providing & Fixing Liquid soap container Providing & Fixing 1/2" C.P. Angular stop (iv)cock (ESSCO -Delux).	10 Nos 1 PC 4 Nos 10 Pcs
5	Providing & Fixing white porcel sink with 1 1/4 C.P. waste and PVC 1 1/4 X 3'0" waste pipe 20" X 16" including C.I. bracket complete.	4 Nos.
6	Providing & Fixing PVC pipe (Supreme)/G.I. pipe with PVC/G.L fittings as require after removing the damage pipe line. 1 1/ I. Pipe line incl. fitting 3/4" G.I. Pipe line incl. fitting 1 1/2 G.I. Pipe line incl. Fitting PVC pipe line incl. PVC fittings line incl. PVC fittings 1/2" PVC pipe line incl. PVC fittings	20Rft 50Rft 120 Rft 30 Rh 40 Rft 80 Rft
7	Providing and flxlng 1/2" C.P. 2 in- 1 Bib cock (Jaguar) withhand shower complete set.	13 Nos.
8	8 Providing and Fixing Eahaust fan with cutting 9" dia hole and making good the damages (Havells). 12" dia 18" da	3 nos. 1 no. 2 nos.
9	Material and Labour charges for malting G.I. 9 sheet duct 12" clia including necessary M.S. clamp, hanger as require 12" dia	
10	10 Providing and Fixing golden fish 6mm mirror 24" X 18" with ply back and C.P. Top Screws	3 Nos.
11	Providing and fixing 8" X 12 " / 12" X 18" wall tiles (Kajaria/J.N.) 1: 3 including fixing the joints after removing the existing cement plaster from wall	

12	Providing and fixing 8" X 12 " / 16" X 16" floor tiles (Kajaria/J.N.) 1: 3 on floor after removing the existing IPS floor and removing *.he debris.	
13	Providing and fixing 24" X 24" Standard quality vitrified tiles (Kajaria) as approved colour (1 3) with cement and sand mortar after removing the existing cement floor	
14	Plastic emulsion paint two coats over a coating of cement 14 primer on wall and ceiling including preparing the surface (Rangoli- Berger)	
15	Synthetic oil paints two coats over a coating of 15 primer work on doors, windows, window , steel shutter including preparing the surface (Luxol-Berger)	