Notice Inviting Quotations for "Interior decoration and Painting work on Ground floor room at Main Building" Gokhale Memorial Girls' College, Kolkata, from the reputed, bonafide and resourceful contractors / firms for the following items/works. The envelope must be sealed & superscripted as "Interior decoration and Painting work on Ground floor room at Main Building". The sealed envelopes should be submitted in the Drop Box placed at the main building entrance from 21/05/2022 to 31/05/2022 between 10.30 a.m. – 4.30 p.m. on all working days. The bidders will be intimated in due time after opening of the quotations

Date: 21/05/22

| Item | Particulars Particulars | Quantity |
|-------|--|------------|
| 1 | Providing and fixing Perforated 12 mm 2'x2' insulation Sitatex | 278.31 |
| | Board under G.I. Frame work complete on Ceiling. | Sqft. |
| | Alternative | |
| | Fixing 12 mm Gypsum Board under G.I. framing on Ceiling | 278.31 |
| | complete. | Sqft. |
| 2.a) | | 916.31 |
| | 1.5mm Putty filling on walls. | Sqft. |
| | Two coats of Plastic emulsion paint (Easy clean-BERGER | 916.31 |
| b) | MAKE) over a coating of cement primer on wall and ceiling | |
| | including sand papering and prepainting. The surface complete. | Sqft. |
| c) | Two coats of Synthetic enamel painting (Luxol-BERGER) over a | 20.0 Sqft. |
| | coating of priming work on window. | |
| 3.a) | Providing and fixing aluminium door frame (Sec. 45x55mm) with | |
| | shutter 45mm upper part 50% by clear glass panes, 5mm and | 20.06 |
| | lower part 12mm both side laminate finish ply including 8" door | |
| | handle both side and locking arrangement, door closure complete. | Sqft. |
| | 1x3'-2"x6'-4" | |
| | Providing and fixing aluminium window frame with 2 nos. 5mm | |
| b) | glazed aluminium shutter with hinges, handle, tower bolt | |
| | complete. 1x4'-0"x4'-9" | 19.0 Sqft |
| 3. a) | Champering and removing the existing IPS top with cleaning the | 322.0 |
| | debris from floor and cutting the 6" skirting from wall area also. | Sqft |
| b) | Providing and fixing 8mm thick ISO Make 2'x2' Plane Cream | |
| | Colour vitrified tiles on floor with Sika adhesive and cement mix | 278.31 |
| | compound including colour cement joints complete. | Sqft. |

| c) | Providing and fixing 6" Vitrified Cream Colour Tiles to skirting | |
|------|--|-----------|
| | on wall with 1:3 cement morter. | 44.0 Sqft |
| 4 | Providing and fixing conceal work for electrical line with | |
| | conduled (15mm) PVC and reparing the plastered wall surfaced: | |
| i) | 1.0mm (ISO) Copper wire laying for 5 Amp electric points | 12 Nos |
| | including Anchor fittings complete on board. | Point |
| ii) | 4.0 mm cCopper Wire (ISO) lahing with 1.0 mm copper wire for | |
| | earthings including 15 Amp soket and AC starter (Anchor- | |
| | Roma) fittings on board. | 1 Point |
| iii) | 4.0 mm cCopper Wire (ISO) lahing with 1.0 mm copper wire for | |
| | earthings including 15 Amp Anchor fittings complete on board. | 2 Points |
| iv) | 10 way M.C.B. Box (Havells) fittings with Isolator & Required | |
| | M.C.B. including necessary electrical line under conduled pipe | |
| | from Distribution Board to point Board. | |
| | | |

TERMS & CONDITIONS:

- 1. Bidders must provide the complete quotation for all of the items/works with their Income Tax/ Sale Tax clearance certificate, GST Registration number & Credentials without which the quotation will be summarily rejected.
- 2. The College reserves the rights to accept or cancel the quotation, unilaterally without assigning any reason prior to work orders without incurring any liability or any obligation and no correspondence from either side in that matter will be entertained.
- 3. The work must be completed within 30 days from the date of issuance of work order. Any deviation in this regard will attract Stop Payment of the bill submitted.
- 4. The bids will be inclusive of charges including GST.
- 5. The materials will be rejected if any defect and/or deviation in quality from specification or of old stock are found.
- 6. Payment will be made after 15 days from the completion the work.