

GMGC/Quotation-03/ washroom construction-1/ 2022-23/80 Date: 21/05/22

Notice Inviting Quotations for “**Materials and labour charges for construction of a washroom attached to main building (size: 7’-0”x 4’-0)”** Gokhale Memorial Girls’ College, Kolkata, from the reputed, bonafide and resourceful contractors / firms for the following items/works. The envelope must be sealed & superscripted as “**Materials and labour charges for construction of a washroom attached to main building (size: 7’-0”x 4’-0)”**. The sealed envelopes should be submitted in the Drop Box placed at the main building entrance from 21/05/2022 to 31/05/2022 between 10.30 a.m. – 4.30 p.m. on all working days. The bidders will be intimated in due time after opening of the quotations

Item	Particulars	Quantity
1	Dismantalling Cement plaster from 2 walls and removing the debris.	77.0 Sqft.
2.a)	Providing and fixing 12"x11" Non-skid tiles on floor (1:3) after dismantalling the existing IPS floor.	28.0 Sqft.
b)	Providing and fixing 13"x15"/18"x12" Plain Colour Ceramic Tiles on wall 1:3 mortar with colour cement joints complete (Mt. 2100 mm) 7'x0".	140.0 Sqft
3.a)	Materials and labour charges for 15 m UPvC pipe line on wall including necessary UPVC fitting after chase cutting on wall and mending good the damages (1:4).	30 Sqft
b)	-do- 37 mm UPVC Waste pipe line for basin with necessary fitting.	7.5 Sqft
c)	Providing and fixing:	
i)	15 mm C.P. Angular Stop Cock with C.P. extn. Pcs and clung (Essco).	2 Nos.
ii)	15 mm 2in 1 C.P. bib cock with hand shower including extn pcs and flunge.	1 No.
iii)	Single Syphonic 'p' Trap water closer white porcelian make with PVC white Low-down cistern and seat cover (Perry/Hindware) fitting with steel screw 15 mm x 600 N PVC connector pipe complete.	1 No.
iv)	White Porceline 550x400 Wash Hand (Perry/Hindware) basin with 15 mm C.P.Pillar Cock (Essco) 15 mm PVC connector pipe, 37 mm C.P. basin waste including PVC waste pipe complete.	1 No.
v)	Fixing 5 mm (Mody Guard) Mirror on W.P. Ply 12 mm thick, Mirror Size 600mm x 600mm.	1 No.

vi)	Fixing C.P. Towel rod (500 mm Length)	1 No.
vii)	Fixing Liquid Soap container.	1 No.
viii)	Fixing glass Guard rail rack.	1 No.
d)	Providing and fixing:	
i)	9" Exhaust Fan.	1 No.
ii)	4'-0" LED Light.	1 No.
iii)	2'-0" LED Tube with Glass cover.	
iv)	Internal electrical line for 3 Nos. (5 Amp) Points with 1.0 mm copper wire under 25 mm PVC conduled pipe.	3 point
e. i)	1 No. coats of synthetic oil paint (Luxol) over a coating of priming work with 1:5 mm putty filling on wall rest part and ceiling.	78.0 Sqft.
ii)	Providing and fixing 25 mm PVC door with frame (Raunag) including aluminium fitting. Size: 2050x750 mm.	1 No.

TERMS & CONDITIONS:

1. Bidders must provide the quotation for all of the items/works with their Income Tax/ Sale Tax clearance certificate, GST Registration number & Credentials without which the quotation will be summarily rejected.
2. The College reserves the rights to accept or cancel the quotation, unilaterally without assigning any reason prior to work orders without incurring any liability or any obligation and no correspondence from either side in that matter will be entertained.
3. The work must be completed within 30 days from the date of issuance of work order. Any deviation in this regard will attract Stop Payment of the bill submitted.
4. The bids will be inclusive of charges including GST.
5. The materials will be rejected if any defect and/or deviation in quality from specification or of old stock are found.
6. Payment will be made after 15 days from the completion the work.