

GMGC/Quotation -04/ washroom construction-2/ 2022-23/81 Date: 21/05/22

Notice Inviting Quotations for Quotations “**Materials and labour charges for construction of a washroom outside the main building**” Gokhale Memorial Girls’ College, Kolkata, from the reputed, bonafide and resourceful contractors / firms for the following items/works. The envelope must be sealed & superscripted as “**Materials and labour charges for construction of a washroom outside the main building**”. The sealed envelopes should be submitted in the Drop Box placed at the main building entrance from 21/05/2022 to 31/05/2022 between 10.30 a.m. – 4.30 p.m. on all working days. The bidders will be intimated in due time after opening of the quotations

Item	Particulars	Quantity
1.a)	Removing the existing damages corrugated Asbestos roof and structure and staging properly.	57.0 Sqft.
b)	Dismantalling the existing cement plaster from inside walls and outside walls.	157.0 Sqft.
c)	Dismantalling the existing toilet damages floors and removing the same with Indian type W.C.	22.0 Sqft.
2.a)	5" Cement brick wall (1:4) to raising the existing toilets height 1'-6".	49.0 Sqft.
b)	Placing R.C.C. Lintel 5"x5" on door opening after removing the existing damage door shutters and frame.	7.0 Sqft.
c)	Cement brick plaster 20mm inside and outside (1:5) adding 10% damp proofing compound.	207.0 Sqft.
d)	Providing and fixing Glazed Tiles (ISO Brand) fitting with 1:3 mortar to wall upto 4'-0" height from inside toilet floor with cement joints complete.	104.0 Sqft.
e)	Providing and fixing Non-skid tiles (ISO Brand) fittings on floor (1:3) on toilets.	32.0 Sqft.
f)	Providing and fixing 1" (25 mm) ISO brand PVC door with frame including necessary fittings (Size: 2'-6" x 6'-0") on toilets.	2 nos.
3	Providing and fixing Corrugated blue scope 'Tala' colour quoted G.I. Sheet under structure of tubular structure (tata make) with fittings complete.	57.0 Sqft.

4.a)	Providing and fixing Orissa type Porcelien White 20" closet with PVC low-down cistern, flash pipe, 1/2" C.P.Angular Stop Cock and connector pipe complete (Perry/Hindware).	1 set.
b)	Providing and fixing european type porcelin white colour water closet with White PVC lowdown cistern, PVC seat cover (Hindware/Perry) including 1/2" C.P. Angular Stop Cock (Essco) connector pipe complete.	1 set.
c)	Providing and fixing 110 mm waste PVC pipe line (Supreme) with PVC fittings 110 mm such as bend, trap, junction etc. and connecting with the existing lines.	L.S.
5	Two coats of Weather coats paint (BERGER Paint) on exterior and interior wall of the toilet over a coating of priming work.	207.0 Sqft.

TERMS & CONDITIONS:

1. Suppliers must provide the quotation for all of the items/works with their Income Tax/ Sale Tax clearance certificate, GST Registration number & Credentials without which the quotation will be summarily rejected.
2. The College reserves the rights to accept or cancel the quotation, unilaterally without assigning any reason prior to work orders without incurring any liability or any obligation and no correspondence from either side in that matter will be entertained.
3. The work must be completed within 30 days from the date of issuance of work order. Any deviation in this regard will attract Stop Payment of the bill submitted.
4. The bids will be inclusive of charges including GST.
5. The materials will be rejected if any defect and/or deviation in quality from specification or of old stock are found.
6. Payment will be made after 15 days from the completion the work.