

**GMGC/Quotation-05/ Pump room renovation / 2022-23/117      Date: 10/06/22**

Notice Inviting Quotations for “**Renovation of the existing pump room**” Gokhale Memorial Girls’ College, Kolkata, from the reputed, bonafide and resourceful contractors / firms for the following items/works. The envelope must be sealed & superscripted as “**Renovation of the existing pump room**”. The sealed envelopes should be submitted in the Drop Box placed at the main building entrance from 10/06/2022 to 18/06/2022 between 10.30 a.m. – 4.30 p.m. on all working days. The bidders will be intimated in due time after opening of the quotations

**Work:-Renovation of the existing pump room: Size: 9'-0" L x 4'-0" N x 3'-9" ht. with height raising 2'-6", so now the total proposed height will be 6'-5", including repairing of pumps and electrical points:**

Item	PARTICULARS	Quantity
a)	Dismantling the existing R.C.C. roof slab 4" thick and removing the debris.	36.0 Sqft.
b)	Removing and cement existing plaster from inside and outside walls with removing the debris.	97.5 Sqft.
c)	250 mm cement brick wall (1:6) with cement and sand mortar.	45.0 Sqft.
d)	125 mm cement brick wall (1:4) with cement and sand including wire netting after three respective layers.	20.0 Sqft.
e)	19 mm cement plaster on inside and outside walls with 1:5 adding 10% damp proofing compound.	325.0 Sqft.
f)	100 mm thick reinforcement cement concrete to R.C.C. slab with shuttering and reinforcement complete.	42.75 Sqft.
g)	Champering the ceiling and 15 mm cement plaster on ceiling and 15 mm cement plaster on ceiling 1:4 mortar.	42.75 Sqft.
h)	Dismantling the existing cement damages flooring and re-construct 75 mm thick the same with 1:2:4. including net cement finish (1:5mm) complete after installation of motor pump.	42.75 Sqft.
i)	Reinforcement cement concrete to R.C.C. lintel 5"X5" with 1:2:4 on both the door opening.	6.0 Sqft.
j)	Providing and fixing 1'2" Angle framed M.S. Sheet door with 2" Angle frame including necessary fittings complete.	28.0 Sqft.

k)	Providing and fixing 15 Amp power point with starter under conducted pipe wiring by 4.0 mm copper wire and 1.0 mm earthing.	2 serts
l)	Labour charges for opening and re-installation of existing 2HP motor pump with fix-bolt, nut washer and re-oiling the motor pump.	1 no.
m)	Repairing the existing motor pump with opening and re-installation including fixing with fix bolt, nut, plate, works to be and re-oiling the same.	1 no.
n)	Water primer on wall and ceiling inside and outside of the pump room with two coats of weather coating complete.	317.75 Sqft.
o)	Two coats of synthetic enamel painting over a coating of red lead priming on sheet gates.	56.0 Sqft.
p)i)	Labour charges for chamfering the top of roof slab.	42.75 Sqft.
ii)	40 mm thick damp proofing treatment on roof top with 1:2:4 adding 10% damp proofing compound including 1.5 mm neat cement finish complete.	42.75 Sqft.

#### TERMS & CONDITIONS:

1. Bidders must provide the complete quotation for all of the items/works with their Income Tax/ Sale Tax clearance certificate, GST Registration number & Credentials without which the quotation will be summarily rejected.
2. The College reserves the rights to accept or cancel the quotation, unilaterally without assigning any reason prior to work orders without incurring any liability or any obligation and no correspondence from either side in that matter will be entertained.
3. The work must be completed within 30 days from the date of issuance of work order. Any deviation in this regard will attract Stop Payment of the bill submitted.
4. The bids will be inclusive of charges including GST.
5. The materials will be rejected if any defect and/or deviation in quality from specification or of old stock are found.
6. Payment will be made after 15 days from the completion the work.